# PROPOSAL FOR INTERNAL WORKS TO UPPINGHAM TOWN HALL

July 2023

Presented by Cllr. Mark Shaw

This Proposal has created in light of the urgency of works required at Uppingham Town Hall following a paper from Sharon Coe – Town Clerk and RFO

In additional to the Clerks paper there is a requirement for the replacement of the current heating systems as the current system is inefficient, old and costly to repair / maintain.

It is recommended that the Town Hall move to infrared heating for the office's, toilets and kitchen areas. Main reasons being they are low maintenance, easy to control and reduces dependances on fossil fuels.

For more information see: <a href="https://www.warm4less.com/news/5-surprising-health-benefits-of-infrared-heating/">https://www.warm4less.com/news/5-surprising-health-benefits-of-infrared-heating/</a>

For future protection and in consideration of future energy requirements it is recommended the town hall be upgraded to 3-phase electricity as it currently has a domestic 100amp supply into the building. Should the town hall install a high-capacity vehicle charger in the future a 3-phase supply will be required.

The recommendations are as follows:

- Refurb kitchen to a similar layout with 5-ring induction hob and two electric ovens
- Refurb 'Bar' area to be open-plan with increased area for tables and chairs. This change of layout will increase flexibility of the area.
- Decorate kitchen and bar areas.
- New flooring to kitchen, toilets, and lobby areas.
- Install Infrared Heating to offices, toilets, kitchen and bar areas
- Upgrade electricity supply to 3-phase electricity.

# Paper from Sharon Coe - Town Clerk and RFO

# Town Hall CIL Funding

This paper has been written following a tour and inspection of the Town Hall with Town Clerk, Sharon Coe. The Town Hall is in a good to moderate state of repair with some minor works needing attention that can be managed through the annual maintenance budget. It was agreed that there were 2 main areas that could benefit from CIL funding

- 1) Kitchen
- 2) Cellar

# Kitchen

Kitchen cupboard doors are peeling drastically, cupboards are damp, visually off-putting, musty smell in the room. Without removing the cupboards, it is not possible to ascertain the condition of the walls and floor.

Estimate to fit new kitchen cupboards/repair/decorate walls and floor: £10k (£15k should problems be found).

# Cellar

Plans to repair and refit the cellar have been ongoing for several years with plans for a Public Works Loan to finance the essential work. There is a need to repair some structural damage and a leaking ceiling. After the repair there are existing plans and quotes to refit the cellar. These refurbishment plans would create much needed storage space for hirers to keep equipment and provide additional storage for the Town Council.

The cellar refurbishment works have been previously approved by Full Council, resolution 364/18. A quotation has also been accepted, resolution 279/19.

Costs c£23k – could apply for part-payment by PWLB and part CIL?

Town Hall hirers were contacted for input and feedback re Town Hall Facilities and highlighted

- 3) Toilets
- 4) Disabled Access

# <u>Toilets</u>

Hirers have described the toilets as "grubby", "unwelcoming", "not up-to-date" but the main complaint has been the lack of heating. A simple electric heater would suffice

# **Disabled Access**

The council began a project re disabled access in 2016.

By 6/3/2019 the project had been approved by FC/F&GP Planning permission granted, quotes received, and architect's drawings paid for plus exploratory groundworks. Grant submission to WREN and council contribution agreed.

Cost in 2019 was £32,800

All projects fulfil the requirement for CIL funding via increased usage of existing facilities.

# Main Hall Suspended Ceiling

The suspended ceiling tiles are beginning to sag and require replacement. A full inspection of the suspended ceiling should be undertaken

# **WORKS REQUIRED**

# Kitchen

- 1 Supply and fit new Kitchen Base & Wall Units as per design and white goods (inc Electric Hob and two ovens)
- 2 Electrical Works
- 3 Plumbing Works
- 4 New Flooring to Kitchen Area
- 5 Make good accordingly & redecorate

# Bar Area

- 1 Supply and fit new Kitchen Base & Wall Units as per design
- 2 Electrical Works
- 3 Plumbing Works
- 4 New Flooring to Bar Area
- 5 Make good accordingly & redecorate

# Cellar

- 1 Electrical Works
- 2 New suspended floor
- 3 New Suspended Ceiling
- 4 Batten walls and line with moisture resistant boards
- 5 Make good accordingly & redecorate

# Communal hallway and toilets to front of Town Hall

1 Replace flooring to all areas

# **Electrical Works**

Install infrared heating to:

- Main Office
- Secondary Office (Police)
- Toilets
- Communal Hall

In addition to the above we will require the following:

- Electrical works as required for kitchen installation
- Electrical works as required for bar installation

# 3-Phase Electric Supply

Additional Electricity Supply Required for future use

Installation of 3-phase electricity – Currently 100amp domestic supply

# Quotations Received for the various works:

# Kitchen, Bar Area & Cellar

1. Marvin Building Services Limited [Toft]

Quotation: £17,215.33 + VAT (See Appendix A)

2. Palmers of Oakham Ltd [Egleton]

Quotation: £17,919.00 + VAT (See Appendix B)

3. Arete Contractors Ltd [Corby]

Quotation: £18,823.96 + VAT (See Appendix C)

# **Kitchen Supply Only**

1. Howdens Kitchen Limited [Corby]

Quotation: £8,355.43 + VAT (See Appendix D)

# Flooring

2. Welland Flooring Ltd [Corby]

Quotation: £10,884.56 + VAT (See Appendix E)

3. Barefoot Flooring Ltd [Oakham]

Quotation: £4,520.54 + VAT (See Appendix F)

# **Electrical Works**

1. Odom Electrical Limited

Quotation: £6,288.28 + VAT (See Appendix G)

# 3-Phase Electricity Supply

1. National Grid

Quotation: £6,656.00 + VAT (See Appendix H)

# FINAL COST AND RECOMMENDATIONS

Kitchen, Bar Area & Cellar Area	
Marvin Building Services Limited [Toft]	£17,215.33
Kitchen Supply Only	
Howdens Kitchen Limited [Corby]	£8,355.43
Flooring	
Barefoot Flooring Ltd [Oakham]	£4,520.54
Electrical Works	•
Odom Electrical Limited	£6,288.28
3-Phase Electricity Supply	
National Grid	£6,656.00
Total	£43,035.58
Project Contingency Fund	
Contingency Fund – 10%	£4,303.55
Total Cost of Project	£47,339.13
VAT	£9,467.83
Total Cost of Project (inc. VAT)	£56,806.96



The Gables, Toft 07376146249 Marvinbuildingservices@gmail.com www.marvinbuildingservices.co.uk @Marvinbuildingservicesltd

# Quote

Project proposal:

Uppingham Town Hall

**Customer name:** 

Mr Mark Shaw

Date:

05/06/2023

Job number:

JOB-188

# Site Work



# **General Preliminaries**

# **General Preliminaries**

- ✓ Photographic Records✓ Initial site set up
- ✓ Tower scaffolding
- ✓ Signage✓ Fire extinguishers and First Aid
- ✓ Small plant
   ✓ Small tools
- ✓ Waste disposal
- ✓ Admin & Supervision ✓ Builders clean



# Demolition / Removal

- ✓ Demolition/removal
- ✓ Disposal surplus materials off site
- ✓ We have allowed for 2 x 8 Yard Skip

# Structure



# Internal Walls

# Timber frame. Timber frame walls above DPC:

- Timber stud work using 47 x 95 mm (2" x 4") treated timber at 400mm centres with head and sole plates and 1 row of noggins
- ✓ 100mm Celotex Insulation GA4100 Board 2400mm x 1200mm or similar insulation board between studs ✓ Structural Plywood 2440 x 1220 x 18mm lining externally
- X Note: Plasterboard or finishes to be measured in wall finishes

# Upper Floor Joists

# Floor. Span - 3 m, floor area - 12 m<sup>2</sup>:

- ✓ Sawn Timber Treated C16/C24 47 x 175mm x 3.0 m softwood timber floor joists at 400mm centres

- Supply and install Sawn Timber Treated C16/C24 47 x 95mm
   Supply and install 22 x Standard Joist Hanger 63mm x 250mm JHA270/63
   2 galvanised mild steel joist straps
   Knauf Earthwool Combi Cut 44 Loft Roll Insulation 100mm (13.89m²) or similar insulation fitted between joists

Page: 1 of 2

# Roof Insulation

# Rafter Insulation, 20 m2

- 100mm Celotex Insulation GA4100 Board 2400mm x 1200mm or similar insulation fitted between rafters
- 60mm Celotex Insulation GA3060 Board 2400mm x 1200mm or similar insulation fitted over rafters

# **Finishes**



# Internal Decorating

# Decorating.

# Preparation

- ✓ Fill holes and cracks, scrape any flakes
- Sand and fill, prepare for decoration
- X Disposal surplus materials not included

# **Decorating Walls**

Walls to be painted with one mist coat and two full coats emulsion in magnolia paint

# **Decorating ceiling**

 $\checkmark$  Ceiling to be painted with one mist coat and two full coats emulsion in white paint

# **Decorating Woodwork**

✓ Prime, undercoat and paint skirting board



# Kitchen

# Kitchen installation includes:

- X Kitchen supplied by client
- Quote includes for fixing. Final price will be adjusted to reflect variation of kitchen

# Subtotal:

VAT @ 20%:

£17,215.33 £3,443.07

Total: £20,658.40

# PALMERS OF OAKHAM BUILDING CONTRACTORS

Palmers of Oakham Ltd, Burley View, Hambleton Road, Egleton, Oakham, LE15 8AE

**Tel:** 01572-722096 **Fax:** 01572-724653 www.palmersofoakham.co.uk

Mark Shaw

**Rutland County Council** 

21st June 2023

Dear Mark Shaw

Please see quote for works at Uppingham Town Hall.

Works to cellar £8,085.00 New joists, flooring, batten walls and line with chipboard. Drop ceiling and ply boarding. 2. Works to the kitchen £3,952.00 Strip out existing kitchen, strip tiles and make good plaster, fit Howdens kitchen supplied by others. 3. Works to bar £2,782.00 Strip out existing and cap off plumbing. Fit Howdens units supplied by others. Option for painting 3 rooms £3,100.00 £17,919.00 VAT @ 20% £3,583.80 Total £21,502.80 (Fixed price for 28 days)

> Directors: AJ Palmer BSc (Hons) Civ Eng Registration England 1338882 VAT Reg No 313 0637 01 Registered Office: 30 Nelson Street, Leicester LE1 7BA



Mr M Shaw Uppingham Town Hall 49 High Street East Uppingham Oakham LE15 9PY

16 July 2023

Dear Mr Shaw

# **Proposed Refurbishment Works**

Thank you for your recent enquiry concerning the above works for which we have pleasure in confirming our proposals and prices as detailed on the attached schedule together with a copy of our insurances.

We have made allowances within our price for:

- ✓ Supervision.
- Mobilisation.
- ✓ Disposal of all surplus materials in compliance with current legislation.

However, we have not included for:

- Diversion, protection or alteration of statutory operators' apparatus or plant.
- \* Handling or removal of asbestos, toxic or other hazardous material.
- × Removal of fridges and freezers.
- Electrical installation or decommissioning works.
- × VAT at the current rate

# **Payment Terms**

A 25% commitment fee is required with your instruction to proceed to secure a "build slot" and secure materials at the tendered rates.

A further payment of 25% is due one week after commencement.

The final balance is due on completion of the project.

We trust the enclosed may receive your favourable attention and should you require any additional information please do not hesitate to contact the undersigned on 07768 020200.

Yours sincerely

for ARETE

W J Boyd

Gretton Brook Road, Corby, Northamptonshire NN17 4BA

T: 01536 260817 M: 07768 020200 E: willie@arete.uk.net Director: W J Boyd Company Reg. No. 7411189 VAT Reg. No. 100 7829 40

		Uppingh: 49 I	am Town Ha High Street Ea Uppingha LE15 9P	st m	ACL/WJB 06.07.
Preliminaries			CE15 9F		£ p
Supervision	1	Item	860.00	E	860.0
Mobilisation (2 visits to site)	1	Item	150.00	£	
Health & Safety	1	Item	150.00		150.0
Method Statements Risk Assessments		I Kem	130.00	£	150.0
Duty of Care - Waste Transfer					
Scaffolding/Access towers	1	Item	235.00	£	235.00
Skips/Disposal	1	Item	900.00	£	900.00
7-2					
.t.	11		Preliminaries	£	2,295.00
Page 1					

		Uppingt 49	High 5	own Hall Street East Ippingham LE15 9PY		ACLWJB 06.07
Bar Room						£ p
Isolate water supply	1	Item	E	255.00		
	1	Item	-	255.00	£	255
Strip out all existing fixture and fittings and remove from site ind Units	1	Item	E	325.00	£	325
Worktops						
Cupboards			1		l	
Shelving						
Sinks and the like						
Remove slash back tiling	1	Item	E	75.00	£	75
Make good disturbed area	1	Item	£	186.00	£	186
Apply "Stain Guard" to damp areas of walls	1	Item	£			
625	1	Rem	L	89.00	£	89
Apply two coats emulsion to walls and ceilings	1	Item	£	435.00	£	435
PC Sum for emulsion paint	1	Sum	£	60.00	£	60
Apply two coats gloss paint to woodwork	1	Item	£	324.00	£	324
PC Sum for gloss paint	1	Sum	£	50.00	£	50.
Fit new Low and High Level Units, Worktop and Bar Leg all as Drawing No 23022105974 dated 20.06.23	1	Sum	£	550.00	E	F.F.O.
Customer to supply all Units, Top and fixture and fittings					E	550
*All electrical work by others*						
11 9, **						
"\						
			İ			
		1	1			
		}		- 1		
			1			
			1			
				1		
				Bar Room	E	2,349.
				EX. INVIII	-	2,543.
Page 2						

Page .

		ppingh: 49 I	tigh S	Street East ppingham LE15 9PY		ACLWJB 06
				LEIS 9F1		£ p
Kitchen						
Isolate water supply	1	Item	£	255.00	£	- ;
Strip out all existing fixture and fittings and remove from site incl	1	Item	£	487.00	£	
Units						
Worktops						
Cupboards				1		
Shelving Sinks and the like						
0.0000000000000000000000000000000000000		*****		135.00	,	
Remove slash back tiling	1	Item	£	125.00	£	
Make good disturbed area	1	Item	£	210.00	£	
Apply "Stain Guard" to damp areas of walls	1	Item	£	100.00	£	
Apply two coats emulsion to walls and ceilings	1	Item	E	525.00	£	
PC Sum for emulsion paint	1	Sum	£	60.00	£	
Apply two coats gloss paint to woodwork	1	Item	E	324.00	E	
			E	50.00	E	
PC Sum for gloss paint	1	Sum	F	50.00	1	
Fit new Low and High Level Units, Worktops, Sinks, Taps, Hob, Oven, Extractor Hood and the like all as Drawing No 23022105392 dated 20.06.23	1	Sum	£	1,540.00	£	1
Customer to supply all Units, Tops, Appliances etc and fixture and fittings						
Plumbing to new sinks	1	Sum	£	158.00	E	
		1				
*All electrical work by others*						
201		1				
		1				
					1	
		1			1	
					li	
(8)					H	
	1				1	
	1				l l	
	1				1	
	1					
					ı	
		1			1	
	1				1	
					_	
				Kitche	E	3

		Uppingh 49	High 5	own Hall Street East Ippingham LE15 9PY	:	ACL/WJB 06.0
Cellar Room						
Wall plates for flooring and ceiling	13	mtrs	£	27.57	£	358
Underfloor joists	35	mtrs	£	21.72	£	760
Ceiling joists	35	mtrs	£	21.72	£	760
21 x 137 PTG floor boards	10	m2	£	68.28	£	682
CLS Studwork to receive plasterboard	43	m2	£	19.25	£	827.
Cavity insulation studiwork	43	m2	E	21.48	E	
12.5mm Vapour Sheild Plasterboard to walls and ceiling with taped joints	43	m2	£			923.
Skimmed plaster internal finish with scrim and beads	43	m2		21.84	£	939
Apply mist coat to new plaster once dried			£	14.43	£	620.
Apply two coats emulsion to walls and ceilings	1	Item	£		£	245.
PC Sum for emulsion paint	1	Item	£	525.00	£	525.
resum of emusion paint	1	Sum	£	60.00	£	60
m, 12						
*No removal, disconnection or alteration of gas metering, pipwork.*						
Page 4			Cel	lar Room	£	6,702.6

		U		am Town Hall High Street East Uppingham		ACL/WJB 06.07.23
Summary				LE15 9PY		£ p
	Preliminariers		Page	1	£	2,295.00
	Bar Room		Page	2	£	2,349.00
	Kitchen		Page	3	£	3,834.00
	Cellar Room		Page	4	£	6,702.61
				Sub total	£	15,180.61
			12%	O/H & Profit	£	1,821.67
				Total	£	17,002.28
			Lump S	um Project total	£	18,823.96
			4	VAT	£	3,764.79
			Lump S	um Project total	£	22,588.75
	-					
(a * 20 m.)						
l <sub>on</sub>						
	Page 5					



ESTIMATE

Date: 15/03/2023 13:27 Account: 1100126094

MARK SHAW

10, Elizabeth Way Uppingham Oakham LE15 9PQ

Cad Plan Number:
Estimate Number: B88/0240107
Estimate expiry: 13/04/2023
Our Operator: Neil
Sales Consultant: Neil

Your Contact:

Contact No: 07875 248133
Your Reference: uppingham council

Qty Pr	roduct				Net	
		Delivery			100.00	
		Kitchen F			45.37	
				450 CC HiLine Base White Cab	178.13	F
1 CS	ST5414	Clerk Gls	Sndstn	450 CC 900 Tall Wall White Cab	152.26 (	F
1 CS	ST5127	Clerk Gls	Sndstn	500 Upgrade CC 4 Dwr Base White Cab	558.62 1	F
1 CS	ST5458	Clerk Gls	Sndstn	1000 CC 900 Tall wall white Cab	292.42 1	F
1 CS	ST5341	Clerk Gls	Sndstn	1000 CC Hiline Cnr Base White Cab	261.84 1	F
				350 CC HiLine Base White Cab	139.39 (	F
				500 Upgrade CC 4 Dwr Base White Cab	558.62 1	F
1 CS		Clerk Gls White Cab		600 Built Under Oven Housing Base	76.77	F
1 CS		Clerk Gls White Cab		600 Built Under Oven Housing Base	76.77	F
1 CS	ST5341	clerk Gls	Sndstn	1000 CC Hiline Cnr Base White Cab	261.84	F
				600 CC HiLine Base White Cab	326.36	F
1 CS	ST540D	Clerk Gls	Sndstn	350 CC Full Height Wall White Cab	106.62	F
3 CS	ST5511	Clerk Gls	Sndstn	500 CC Standard Height Wall White Cab	393.69 (	F
		Cab		600 CC Integrated Mwave Housing White	158.01	F
3 CS	ST5933	Clerk Gls	Sndstn	910 Base Decor End	67.83	F
3 CS	ST5944	Clerk Gls	Sndstn	752 Full Height Wall Decor End	53.70	
4 CS	ST5947	Clerk Gls	Sndstn	932 Tall Wall Decor End	82.52 1	
2 CS	ST5924	Clerk Gls	Sndstn	Continuous Plinth 3m	38.16 (	F

Depot: Corby Manager: Dom Clarke
Address: Unit 2, Phoenix Trading Centre, Pilot Road, CORBY, NN17 5YF
Tel: 01536 202 289
E-mail: corby@howdens.com

Business Address: as above Online: www.howdens.com

VAT Reg: GB 379 5785 77

Account queries and settlement: Howden Joinery Limited, The Yard, Warth Park Way, Raunds, Wellingborough, NN9 6RJ. Tel: 01604 876000

Howden Joinery Limited. Registered Office: 40 Portman Square, London, W1H 6LT Registered in England No: 526923



ESTIMATE

Date: 15/03/2023 13:27 Account: 1100126094

Estimate For:

MARK SHAW 10, Elizabeth Way Uppingham Oakham LE15 9PO

Cad Plan Number:

Estimate Number: B88/0240107 Estimate expiry: 13/04/2023 Our Operator: Neil Sales Consultant: Neil

Your Contact:

Contact No: 07875 248133 Your Reference: uppingham council

-----Qty Product Net 156.60 F 110.81

9 CST591A Clerk Gls Sndstn Cornice/Pelmet Square Profile 2.4m
1 HJA2986 S/Steel Splashback 900mm
1 LAM2412 Lamona S/Steel Chimney Extractor 90cm
1 LAM2003 Carbon Filter - LAM2412/13,2507,2803/04
1 LAM1902 Lamona Black Touch Ctrl 5 Zone Induction Hob 80cm
2 LAM3410 Lamona S/Steel Single Fan Oven 60cm
2 TAP2486 Chrome Aniene Single Lever Tap
1 SNK1423 Lamona S/Steel Round Inset 1.0 Bowl Sink and Waste
1 PLUI002 Plumbing Kit for 1.0 Bowl Sinks with 1 x Appliance T 132.90 23.89 444.15 386.70 131.40 104.23 1 SNK1423 Lamona S/Steel Round Inset 1.0 Bowl Sink and Waste
1 PLU1002 Plumbing Kit for 1.0 Bowl Sinks with 1 x Appliance Trap
1 SNK6972 Lamona Pitsford S/Steel 1.0 Bowl Sink and Waste
1 LAM7200 Lamona S/Steel Wall Mounted Microwave 38cm
3 WHT5660 Grey Concrete Effect Square Edged Worktop 3m 38mm
1 WOR9029 Stone Grey Worktop Jointing Compound
2 WHT5696 Grey Concrete Effect Worktop Edging Strip 1.4m 38mm
6 GIR0026 Zipbolt Worktop Connecting Bolt
2 CST5231 Clerk Gls Sndstn 600 CC HiLine Base White Cab
4 CST5438 Clerk Gls Sndstn 600 CC 900 Tall Wall White Cab
1 CST5458 Clerk Gls Sndstn 1000 CC 900 Tall Wall White Cab
2 CST5989 Clerk Gls Sndstn Breakfast Bar Backing Panel
1 HYE9627 S/Steel Breakfast Bar Support Leg 10.48 105.47 252.74 597.60 F 43.18 18.48 326.36 F 719.04 F 292.42 F 90.44 F 150.72 F 1 HYE9627 S/Steel Breakfast Bar Support Leg 1 WHT5667 Grey Concrete Effect Square Edged Worktop 3.6m 38mm 1 CST5991 Clerk Gls Sndstn Edging Pack 30.22

Depot: Corby Manager: Dom Clarke
Address: Unit 2, Phoenix Trading Centre, Pilot Road, CORBY, NN17 5YF

Tel: 01536 202 289 E-mail: corby@howdens.com

Business Address: as above

VAT Reg: GB 379 5785 77

Account gueries and settlement: Howden Joinery Limited, The Yard, Warth Park Way, Raunds, Wellingborough, NN9 6RJ. Tel: 01604 876000

Registered Office: 40 Portman Square, London, W1H 6LT Registered in England No: 526923



ESTIMATE

Date: 15/03/2023 13:27 Account: 1100126094

Estimate For:

MARK SHAW 10, Elizabeth Way Uppingham Oakham

LE15 9PQ

Cad Plan Number: Estimate Number: B88/0240107 Estimate expiry: 13/04/2023 Neil

Sales Consultant: Neil

Your Contact:

Contact No: 07875 248133 Your Reference: uppingham council

Qty Product

1 TLS9990 Kitchen Fitters Pack

Net 48.86

Only Products marked F (FSC) or P (PEFC) above Are certified as Follows : FSC Mix 70%, SA-COC-001813 70% PEFC Certified, SA-PEFC-COC-001813

Total Goods 8355.43

1671.09

Estimate Total All prices are in GBP


10026.52

Depot: Corby Manager: Dom Clarke Address: Unit 2, Phoenix Trading Centre, Pilot Road, CORBY, NN17 5YF


Tel: 01536 202 289 E-mail: corby@howdens.com

Business Address: as above Online: www.howdens.com VAT Reg: GB 379 5785 77

Account queries and settlement: Howden Joinery Limited, The Yard, Warth Park Way, Raunds, Wellingborough, NN9 6RJ. Tel: 01604 876000 Howden Joinery Limited. Registered Office: 40 Portman Square, London, W1H 6LT Registered in England No: 526923



https://my-kitchen.howdens.com/plan/lgB8802482622Srf



CARPET AND HARDWOOD SPECIALISTS . THERMOPLASTICS . RUBBER . VINYL . CERAMIC TILES . LINOLEUM . CORK



# WELLAND FLOORING

Company (Corby) Ltd





Uppingham Council 49 High Street East Uppingham LE15 9PY

25th July 2023

Estimate 31255K

## Re: Flooring

We thank you for your enquiry and have pleasure in submitting the following estimate

Lift and dispose of existing slip resistant flooring, supply Latex smoothing compound and skim solid subfloor with one coat of smoothing compound or supply, lay and spotnail SP101, 5.5mm thick plywood over existing timber subfloor Supply and flat lay Gerflor Tarasafe Ultra slip resistant flooring using an approved adhesive and hot welded joints, supply and fit standard aluminium doorstrips where required, all to areas as below

Ladies, Disabled Wc's and Wc lobby including supply and fitting of cove former and forming of integral coving

3155.00

£

Existing Kithcen

1695.65

1st floor kitchenette (fitting up to kitchen cupbaord doors and 1st floor walkway including replacing 3 no nosings

2813.50

Gents Wc's and Lobby including supply and fitting of cove former forming integral coving and new nosing to step

3220.50

NB

- 1 Above prices do not include removal and replacement of existing sanitaryware, pipework in male wc to enabble fitting of new flooring
- 2 All door trimming to be carried out by yourselves

Terms - 50% deposit with order, balance upon invoice

E & O.E

Yours faithfully, for Welland Flooring Co. (Corby) Ltd.

Kalvis Krumins









Registered in England 1963. Registration No. 759003 VAT No. 119 1689-54 Directors. Mylos Knauer, Ed Knauer, Agris Krumins, Kalvis Krumins



Unit 14 Midland Court Station Approach Oakham **LE15 6RA** Tel: 01572759752

www.barefoot-flooring.biz - info@barefoot-flooring.biz

# **Flooring Estimate**

Uppingham Town Hall 49 High Street East Uppingham Oakham **LE15 9PY** 

Reference: Date:

**BFQ-5175** 19/07/2023

Fit Date:

Email:

Tel: 07875 248133

Item	Unit Cost	Qty	Total
WC's, Kitchen, Top Corridor , Vinyl , Altro Walkway , All Colours			£ 1290.00
Floor prep , Floor Stripper Hire , Per Day			£ 108.33
Fitting Charge , Uplift , Bonded Flooring			£ 271.00
Adhesive , Primer , Grip 360			£ 125.00
Screeding , Tilemaster , Pro Flow			£ 408.38
Fitting Charge , Screeding Labour , Square Metre			£ 312.50
Adhesive , FBall , F44			£ 125.00
Fitting Charge , Vinyl Fitting , Full Stick Vinyl			£ 483.75
Carpet (Commercial) , CCF1 Cap & Cove Former			£ 320.95
Fitting Charge , Cap & Cove Lin Mt , Ln Mtr			£ 189.70
Adhesive , F Ball , F3			£ 75.00
Door Bars , Stair Nosing , HB1 Black Insert			£ 37.50
Door Bars , Aluminium Sticky Cover .91 , Aluminium			£ 20.01
	Sub Total		£ 3767.12
	VAT Total		£ 753.42
	Total		£ 4520.54

Please make yourselves aware of our T&C swhich are attached to your Estimate/Invoice. Reuse existing nosings on steps. Cap n Cove in WC's only.

Direct PaymentsRerefoot Flooring Ltd - Starling Bank Acc No 48747057

Sort 608371

With Above Reference

Please note that any additional works such as door trims, moving furniture and uplift of existing flooring will be chargeable unless previously arranged.

Please ask instore about the various services we provide.







Registered No: 08198957

VAT No: 152866002

### **Terms & Conditions**

Barefoot Flooring is a small family run business, we always operate on a basis of trust and open communication.

We do however, think it will be useful to be clear about what you can expect from us, and about what we expect from you.

If you ever think that we have fallen short in your expectations, please pick up the phone and speak to us about it. Above all, your rights under the Consumer Rights Act 2015 will be adhered to.

### **Legal Title**

The legal title of the goods set out in the invoice shall remain the property of Barefoot Flooring Ltd (The Company) until all monies owed are paid in full.

## Deposits & Balances

Your deposit will cover the materials and will be due by return. Any delays with deposit payment may affect your installation date if its already booked, as your goods are ordered once the deposit is paid.

Any balance payments must be paid within 48 hours of completion of works or receipt of the final invoice.

Commercial invoices are to be settled within 7 days or the agreed terms.

We reserve the right to charge a 4% surcharge on late payments

### Cancellations

If you wish to cancel your order, please contact us as soon as possible. If goods have been despatched or cut to your specific size, then it is unlikely that it can be returned, and the cost of goods will be deducted from any advance payment made. Were we provide a supply only purchase, we do not accept returns unless the goods are faulty.

Fitting Services

All fitting is carried out by professional subcontracted tradesman and where free fitting promotions are advertised, the Company shall provide a discount from the cost of goods to be paid to the fitter upon completion of work.

We will always endeavour to meet any arranged fitting dates and times; however, we cannot be held responsible for circumstances beyond our control and/or losses arising from a missed appointment. We would recommend making the day available to receive the fitters and have the work completed. In the unlikely event that we have to reschedule a fitting/delivery date we will inform you at the earliest opportunity to find a mutually agreeable date.

Your invoice/quotation will stipulate the products and services we will supply. Any other services such as door easing, moving furniture, uplift and disposal of existing flooring are not automatically included unless previously arranged and noted on your invoice/quote. Please note that these services are provided at an extra cost.

When providing a quote for new flooring, we will always try and establish the condition of your subfloor. However, until the existing floorcovering is fully removed it is impossible to fully asses it s condition and therefore if any further related costs would be involved. We will, however, keep you informed at every stage if anything arises over and above our initial inspection. On occasion, it may be necessary to provide additional subfloor preparation materials in addition to whats been estimated/quoted. This may be for a variety of reasons that are unforeseen, and will be chargeable in accordance with what s required to complete the work.

Please let us know in advance of any cables/pipes beneath the surface of the subfloor and their location if known. We cannot be held responsible for damage to water, gas, electrical services if we are not made aware beforehand.

We ask that rooms are clear of furniture and old floorcoverings prior to fitting (unless previously arranged). Where we are called upon to help move difficult items of furniture that haven t been possible to move prior to our arrival we cannot be held responsible for breakages and or damage. Kitchen appliances and other electrical goods will need to be disconnected and removed prior to fitting.

The fitting of flooring can be a very aggressive process and while our fitters will take every care not to cause unnecessary marks and scuffs to your door, sometimes this is inevitable. If you have just redecorated, then please be prepared to touch up if necessary. Our fitters are fully insured should any major damage be caused through their negligence.

Our fitting services are guaranteed for a period of 2 years. However, if we visit to rectify an issue which hasn t been caused during the original installation of the flooring, then a charge of £65 will be made, plus rectification costs of which you will be advised of before work commences.

All the samples in store are representative of the manufacturers products and therefore may differ slightly (within tolerances) from the flooring supplied. This is especially relevant in the case of natural flooring & wood.

All soft flooring coverings, whatever their quality, method of construction, pile content may show shading when in use. This is perfectly normal and a characteristic of textile material. The shaded area does not affect the quality or wear/life of the product and is not a fault of the manufacturing process.

## Post Install Care

Barefoot Flooring are not liable for any damage or issue is arising post installation where other trades are still work onsite, or where furniture is being re-sited etc. We recommend the flooring be professionally cleaned and all flooring types be maintained in accordance within the manufacturer is guidelines. In no circumstances should a steam mop be used to clean any floorcovering regardless of the instructions and suitability of use from the steam mop manufacturer.

Privacy Policy

At Barefoot Flooring, we take your privacy seriously and only use your details to administer your account and provide details of the products & services you have requested. We may share your details with our contractors so that the may carry out the work we have agreed and liase directly with you should the need arise.

We may use your information to keep you posted about any other offers or promotions. Let us know if you d prefer us not to.



<b>Customer Name</b>	Address	Date	Quote Number
Mark Shaw	Uppingham Town Hall	11/04/23	1504

# Quotation

# Dear Mark,

Further to our recent conversation, I have pleasure in submitting the following quote for your approval.

I understand the nature of the project and therefore I will be flexible to accommodate your needs. If you would like to talk about any area of the quote with regards to schedule and time etc., please do not hesitate to call me. All accessories will be in finished in white plastic, unless stated.

# Electrical work to be carried out as discussed:

# General:-

1) Supply and install 1 x 12 way RCBO fuse board with SPD compliant with BS7671

# **HEATING:-**

# Office:-

- 1) 2 x 1200watt heating panels.
- 2) 1 x PIR to operate panels.

# **Police Office:-**

- 1) 2 x 1200watt heating panels.
- 2) 1 x PIR to operate panels.

# Ladies toilet:-

- 1) 1 x 350 watt heater.
- 2) 1 x PIR to operate heater.

1 Richil Court, Ayston Road, Uppingham, Rutland LE15 9RL Mobile: 07792 295 355 Telephone: 01572 345163

Email: edward@odomelectrical.co.uk Website: www.odomelectrical.co.uk

Odom Electrical Limited. Registered in England. Company No. 10457979. Director: Mr E.H.J. Odom





# Ladies toilet:-

- 1) 1 x 350 watt heater.
- 2) 1 x PIR to operate heater.

# Disabled toilet:-

- 1) 1 x 580 watt heater.
- 2) 1 x PIR to operate heater.

# Hallway:-

- 1) 1 x 580 watt heater.
- 2) 2 x 900 watt heater.
- 3) 1 x PIR to operate heaters.

# Kitchen:-

- 1) 2 x 1200 watt heating panels.
- 2) 1 x PIR to operate heaters.

# New lounge Area:-

- 1) 2 x 1200 watt heating panels.
- 2) 1 x PIR to operate heaters.

All work will be NICEIC certified and guaranteed.

Labour and Materials:-Sub Total = £6,288.28p

+20% VAT = £1,257.65p

Total = £7,545.93p

1 Richil Court, Ayston Road, Uppingham, Rutland LE15 9RL Mobile: 07792 295 355 Telephone: 01572 345163

Email: edward@odomelectrical.co.uk Website: www.odomelectrical.co.uk

Odom Electrical Limited. Registered in England. Company No. 10457979. Director: Mr E.H.J. Odom





# nationalgrid

# **Budget Estimate**

Cynthia Ondeng Uppingham Town Council Business 49 HIGH STREET EAST UPPINGHAM OAKHAM LEICESTERSHIRE **LE15 9PY** 

National Grid Electricity Distribution National Grid Isaac Newton Way Alma Park Industrial Estate GRANTHAM Lincolnshire NG31 9RT

Our ref 4688871 Telephone: 01476863069 Email: ascooper@nationalgrid.co.uk 25/04/2023

Dear Cynthia Ondeng Uppingham Town Council Business,

Budget Estimate for electricity connection works by National Grid Electricity Distribution (East Midlands) plc ("NGED") for a 45.00kVA Connection at 49 High Street East, Uppingham, Oakham, Leicestershire LE15 9PY

Thank you for your recent enquiry. I am pleased to provide an indication of NGED's likely costs to carry out the connection works for you ("the Budget Estimate").

Our estimate for this work is based upon the information you have provided and is shown below.

Estimated Connection Charge	Contestable works	£ 6,656.00
	Non-Contestable works	£ 163.00
	VAT at 20 %	£ 1,364.00
	Total	£ 8,183.00

Non-Contestable works are those works that only NGED can undertake. It is possible for you to get someone else to quote for the contestable part of the works. For further information please visit our website: <a href="https://nationalgrid.co.uk/Connections/Competition-in-Connections.aspx">https://nationalgrid.co.uk/Connections/Competition-in-Connections.aspx</a>

# Your supply will have the following electrical characteristics

Voltage	230 / 400 Volts
Phase	Three Phase
Agreed Import Capacity	45kVA
Agreed Export Capacity	OkVA

Please note that the proposed works and estimated connection charge is for **guidance purposes** only and has been derived from a desk-top design exercise. It is non-binding and subject, in particular, to any legal permission, wayleaves and any other consents being successfully obtained. It is based on present day prices. It does not include the cost of any necessary on-site civil works, which should be provided by you at your expense.

# **Enclosures**

# Please also find enclosed:

- Our summary document entitled "Budget Estimates Your Budget Estimate Explained" A drawing showing the indicative point of connection (POC) of the new assets to our existing distribution system, in

relation to the proposed development.

## **Competition in Connections**

The Budget Estimate is based upon NGED undertaking both the contestable and non-contestable connection works. You are able to seek competitive prices for some or all of the contestable elements.

You have the option to appoint an Independent Connection Provider (ICP) or Independent Distribution Network Operator (IDNO) to carry out some of the connection works, referred to as the Contestable Connection Works. Any connection works that can only be undertaken by NGED are referred to as Non-contestable Connection Works. See our enclosed Budget Estimate guide for more information.

# **Proposed Connection Works**

# Our estimate of the connection charge is for providing the following works:

Please note that these proposals are based upon a desk top provisional investigation and no site visit or detailed study has been carried out

The estimate does not include costs for any reinforcement or diversionary work that may be required, or for any environmental, or stability studies which may also be necessary, although these are generally only required for larger capacity connections.

# **Progression to Connection Offer stage**

This Budget Estimate is not a legally binding contract, but sets out the amount we reasonably estimate we would require you to pay for the connection works under a formal Connection offer.

If you would like us to undertake a more detailed analysis, including an assessment of any network reinforcement required we can provide a formal Connection Offer. Further information regarding how to apply is provided in our enclosed summary guide.

Upon receipt of your application we will carry out detailed network studies to finalise the design of the connection works (and any associated reinforcement works), and provide a Connection Offer detailing the works required, the associated costs, timescales, payment terms and conditions for the connection.

If you have any queries regarding this Budget Estimate please do not hesitate to contact me via the contact details at the top of this letter.

Yours sincerely.

Ashley Cooper Planner

